

60mblk home ba

60-CELL MONOCRYSTALLINE MODULE



310 Wp

MAX POWER OUPUT

18.8%

MAX EFFICIENCY

10 YEAR

PRODUCT WARRANTY

25 YEAR

LINEAR PERFORMANCE GUARANTEE

HELIENE INC. IS A PREMIER SOLAR MODULE MANUFACTURER, SERVICING THE GROWING SOLAR ENERGY MARKETS OF NORTH AMERICA.

COMBINING PROVEN EUROPEAN TECHNOLOGY WITH NORTH AMERICAN INGENUITY ALLOWS HELIENE TO MAKE A REAL COMMITMENT IN PROVIDING SMARTER ENERGY CHOICES FOR THE FUTURE.

HELIENE

www.heliene.com





GUARANTEED POSITIVE POWER SORTING: [-0: +4.99 WP]



AVAILABLE IN 1000V OR 1500V SYSTEM VOLTAGE RATING



MANUFACTURED FOLLOWING INTERNATIONAL **QUALITY SYSTEM STANDARDS: ISO9001**




H-BLACK INTEGRATION AVAILABLE (ALL-BLACK MODULE)


LINEAR PERFORMANCE GUARANTEE

10 YEAR WORKMANSHIP WARRANTY • 25 YEAR LINEAR PERFORMANCE GUARANTEE






DIMENSIONS FOR 60M HOME PV SERIES



I-V CURVE FOR HELIENE 60M HOEM PVSERIES



CERTIFICATIONS





ELECTRICAL DATA (STC) Peak Rated Power P_{mpp} (W) 310 305 300 295 33.44 34.14 33.72 33.42 Maximum Power Voltage $V_{mpp}(V)$ Maximum Power Current I_{mpp} (A) 9.66 9.62 9.56 9.53 40.13 40.08 39.63 39.22 Open Circuit Voltage V (V) **Short Circuit Current** Isc (A) 10.22 10.17 10.10 10.09 Module Efficiency * Eff (%) 18.78 18.48 18.18 17.88

20

20

[-0, +4.99] Wp

20

20

STC - Standard Test Conditions: Irradiation 1000 W/m2 - Air mass AM 1.5 - Cell temperature 25 °C

* Calculated using maximum power based on full positive output tolerance [-0, +4.99] Wp

MF (A)

MECHANICAL DATA

Maximum Series Fuse Rating

Power Output Tolerance

Dimensions (L x W x D)	1666 x 1001 x 40 mm (65.5 x 39.4 x 1.6 inch)
Weight*	22 kg (48.5 lbs)
Output Cables	1.0 m (39.4 inch) symmetrical cables with MC4 type connectors
Junction Box	IP-67 rated with bypass diodes
Frame	Double webbed 15 micron anodized aluminum alloy
Front Glass	Low-iron content, high-transmission PV solar glass
Solar Cells	60 Monocrystalline cells (159 x 159 mm)

* Calculated using 3.2mm PV glass, if 4mm profile is requested weight load will vary

CERTIFICATIONS

UL Certification	ULC/ORD-C1703-1, UL1703
IEC Certification	Optional

All Heliene modules are certified under the California Energy Commision (CEC) Listing Report

TEMPERATURE RATINGS

Nominal Operating Cell Temperature (NOCT)	+45°C (±2°C)
Temperature Coefficient of P _{max}	-0.38%/°C
Temperature Coefficient of V _{oc}	-0.36%/°C
Temperature Coefficient of I _{sc}	0.07%/°C

MAXIMUM RATINGS

Operational Temperature	-40°C - +85°C	
Max System Voltage	1000V (*1500V)	
	*Optional	

WARRANTY

10 Year Manufacturer's Workmanship Warranty 25 Year Linear Power Guarantee

(Refer to product warranty page for details)

PACKAGING CONFIGURATION

	Modules per box:	26 pieces
	Modules per 53' trailer:	936 pieces

LIENEGOMBLK_HOME PV-Rev.00





